



WESTFIELD

FEATURES FOR SEMIS

GENERAL

1. All interior finishing materials are to be chosen with the assistance of Great Gulf Interior Design Consultants.
2. All materials and other selections for which the Purchaser is entitled to make a selection are to be chosen from Vendor's samples and are as per Vendor's specifications. Purchaser shall only be entitled to make such selections provided that the items are not already ordered or installed.
3. All exterior finishes and colours are selected by the Vendor and are subject to architectural control.
4. Homes are covered with Taron Warranty Corporation's warranty; fee to be paid for by Purchaser on closing.
5. All homes to have blower door test.
6. All homes are third party tested and inspected.

EXTERIORS

7. All model types will be principally brick construction on the first and second floors, as per applicable model elevation.
8. Some sections of the house may be constructed of architectural stone, aluminium or vinyl siding, wood or stucco, as per architectural detailing.
9. Acoustically treated stud party wall between units.
10. Soldier coursing, brick arches, keystones and other masonry detailing as per model / elevation.
11. All soffits, fascias, eaves and down pipes are prefinished aluminium or vinyl at the option of the Vendor.
12. Exterior house address number.
13. Self-sealing limited lifetime warranty laminate shingles.
14. Weather-stripping on all exterior doors and precast stone thresholds.
15. Fibreglass insulated front entry door and "steel-clad" side entry door (as per applicable model/elevation). Glass insert in front entry door, as per applicable/model elevation.
16. All sliding patio doors to be double-glazed, PVC, with low E glass (as per applicable model/elevation)
17. All windows are to be triple glazed, PVC, with low-E glass. All operating windows are to be screened. All operable windows on the first and second floors will be casement throughout with decorative bars on the front elevation, as per applicable model/elevation.
18. All basement windows to be sliders, double-glazed, PVC, with low-E glass. Corrugated galvanized steel window wells may be required as per grading conditions.
19. Garage overhead metal/insulated door(s) with glazed inserts as per applicable model/elevation.
20. All garage walls to be completed to drywall and primed.
21. Front, rear and side yards, if applicable to be fully sodded. Some side yards to be stone, as per grading conditions.
22. Concrete front entry steps, as per grading conditions.
23. Precast concrete slab walkway to front entry.
24. Exterior cold water tap installed in attached garage and at rear of house, as per applicable model/elevation.
25. Basement to be poured concrete with a drainage layer system and a footing barrier membrane.
26. Vendor will provide a two-coat asphalt driveway at a cost more particularly set out in the Schedule B to the Agreement of Purchase and Sale. Driveway surface to be paved with base coat asphalt within eighteen (18) months of closing and the topcoat to be completed within the next calendar year. Vendor not responsible for minor settlement.
27. All exterior walls, interior partitions and flooring are built using H+ME Technology.

INTERIORS

28. Semis model types to have approximately 9 ft. ceiling heights on the main floor and 8 ft. ceilings on second floor, except where precluded by bulkheads.
29. Finished oak stairs with railings, metal pickets on main floor staircase to second floor with a choice of stain from vendor's standard selection.
30. Two panel square style interior doors.
31. 3" casings on all windows and doors
32. 5 ¼" baseboards (with shoe mould in tiled and hardwood areas)
33. All closets to have wire shelving.
34. Satin nickel coloured finish hardware on all interior and exterior doors. Dead bolt on side door entry where applicable. Grip set with dead bolt on main entry door, and single lever handles on interior doors.

35. All paint is zero VOC throughout the house.
36. Sprayed stippled ceiling with smooth border in all rooms except the kitchen, bathrooms and laundry room, which are smooth finish.

FLOORING

37. High performance engineered flooring system "I" - joists.
38. O.S.B. Tongue and groove sub floor glued, nailed, and sanded.
39. 3" Prefinished engineered strip hardwood flooring with choice of colour from vendors standard selection, in all areas of the main and second floor, except where shown as tile, as per applicable model/elevation.
40. Floor tile approx. 12" x 24" in foyer, laundry area, and all bathrooms, or as shown on applicable model/elevation.

KITCHEN

41. Choice of finished kitchen cabinets with a dishwasher opening.
42. Single lever chrome flow efficient faucet with a pull-down sprayer.
43. 2 cm engineered quartz countertops for kitchen with a square edge (No backsplash) and a double stainless steel undermount sink.
44. Stainless Steel ducted range hood fan over stove.
45. Rough-in plumbing and electrical outlet for dishwasher.
46. Wiring and receptacle for stove.
47. Electrical outlets are located for fridge and at counter level for small appliances.

BATH/PLUMBING

48. Choice of vanity cabinets and 2 cm engineered quartz counter tops with a white undermount sink in all bathrooms from Vendor's samples.
49. All bathroom(s) to have a wall-mounted mirror and vanity cabinet as per applicable model / elevation.
50. Ensuite bathroom to have a wall mounted mirror and vanity cabinet with one top drawer as per applicable model/elevation.
51. Master ensuite bathroom to include a white drop-in acrylic soaker tub with a deck mount faucet as per applicable model. Soaker tub to have a tiled deck and skirt with tile on surrounding wall approximately 18" in height.
52. Master ensuite bathroom to contain a separate framed glass shower enclosure, preformed shower base, walls to be tiled to ceiling, per applicable model/elevation, including waterproof pot light.
53. All bathtub enclosure walls in bathrooms to be tiled.
54. All bathtubs to be white acrylic, as per applicable model/elevation.
55. All toilets are to be white, elongated, flow efficient and regular height.
56. Exhaust fan in all bathrooms, vented to the exterior.
57. Privacy locks on all bathroom doors.
58. Single lever chrome flow efficient faucets on all sinks, except laundry tub.
59. Temperature control valves in all showers.
60. Chrome towel bar and toilet paper dispenser in all bathrooms.
61. Main floor powder room to contain a floating vanity cabinet with 2 cm engineered quartz countertop, a white undermount sink, toilet and wall-mounted mirror.
62. Shut off valves for all sinks and toilets.
63. All water lines to be polyethylene tubing throughout.
64. Rough-in three-piece plumbing in basement for future bathroom (drains only, no water lines).

LAUNDRY

65. Second floor laundry room equipped with floor drain as per applicable model/elevation.
66. Laundry room to have a laundry tub or base cabinet with built-in single compartment laundry tub with a two-handle laundry faucet and laminate counter-top, as per applicable model/elevation.
67. Plumbing and electrical outlet for washing.
68. Dryer vent and electrical outlet for future dryer.

ELECTRICAL

69. 200 amp. electrical service.
70. Copper electrical wiring throughout.
71. Electric light fixtures with LED bulbs provided in all rooms except living room, as per applicable model/elevation.
72. Exterior cast aluminium lights with LED bulbs at all exterior doors, as per applicable model/elevation.
73. Two exterior waterproof ground fault circuit Interrupter (GFI) electrical outlets: one (1) at the rear of the house and one (1) in the porch area.
74. White Decora style switches and outlets throughout.
75. Electrical outlet for future garage door opener(s). One outlet for each garage door.
76. Smoke detectors with strobe light hard wired to the electrical system, as per applicable code requirements.
77. Combination smoke detector / carbon monoxide detector hard wired to the electrical system, as per applicable code requirements.
78. Door bells to be installed at front entry /side entry doors as per applicable model.
79. Rough-in vacuum system, located in the basement for future connection as per applicable model/elevation.
80. Rough-in security as per Vendor's specifications (wires to all operable windows and doors on main floor only).
81. Rough-in RG6 cable in family room, master bedroom, loft and study/den, as per applicable model/elevation.
82. Rough-in CAT5 telephone as per Vendor's specifications (one in kitchen, family room, all bedrooms, and den).
83. Rough-in conduit for future installation of an electric vehicle charger located in the garage.
84. A single ground fault interrupter (GFI) protected electrical outlet in all bathrooms.
85. Rough-in conduit for future solar energy.

HEATING, AIR CONDITIONING & INSULATION

86. Direct vent gas-fired high-efficiency forced air furnace with ECM (Electronically Commutated Motor) and includes a programmable thermostat installed. Hot water heater on a rental basis. Note: All mechanical equipment locations may vary from plan.
87. Heat Recovery Ventilator (HRV) as per the Ontario Building Code requirements
88. HVAC ducts are sized for future addition of air conditioning.
89. All insulation to be as per the Ontario Building Code requirements.
90. Basement insulation to be installed to within approximately 8" above the basement slab in the basement area. Note: Basement walls are not strapped.
91. Spray foam insulation to garage ceiling below any habitable space above.

GENERAL PROVISIONS

92. The Purchaser hereby acknowledges and agrees that due to, without limitation, grading, drainage, building code requirements, municipal setback requirements, or other conditions or issues, the Vendor, in its sole discretion, may make changes to modify the floorplan, add and/or adding and or/eliminate doors or steps without adjustment to the purchase price and without further notice to the Purchaser, including without limitation:
 - a. Eliminating the door between the garage and the laundry/utility room;
 - b. Eliminating the side door;
 - c. Installing step(s) with or without a railing in the garage due to different grading may interfere with or limit the use of the interior of the garage;
 - d. Lowering or creating a step down into the laundry/utility room to accommodate the garage door and/or side door to the laundry/utility room;
 - e. Lowering or creating a step down into the foyer
 - f. Installing or eliminating a deck depending upon the grading requirements for that particular lot;
 - g. Entry steps may be required, varied, and/or eliminated to the house.

93. The Purchaser acknowledges that finishing materials contained in any model home or sales office display including but not limited to, broadloom, furniture, electrical fixtures, drapes, ceramic flooring, upgrades kitchen cabinets, stained staircases, railing, wallpaper, paint, landscaping and fencing, may be for display purposes only and may not be of the same grade or type, or may not be included in the dwelling unit purchased herein.
94. Interior design consultation at The Design Studio on all finishes and colour packages included in purchase price. All interior floor, wall finishes and materials are to be chosen with the assistance of the Vendors Interior Design Consultant. All materials and other selections for which the Purchaser is entitled to make a selection are to be chosen from Vendors samples, and are as per Vendor's specifications. Purchaser shall only be entitled to make such selections provided that the items are not already ordered or installed.
95. Purchaser acknowledges the right reserved and/or easement in favour of the Vendor permitting entry for installation of berms, fences and/or landscaping, and the purchaser further acknowledges their undertaking to maintain the berms, fences and/or landscaping after installation.
96. The Purchaser acknowledges that the Vendor will only replace any obvious floor tile damages caused by settlement within the first year of closing, provided the Vendor is able to match the floor tile dye lots, colours and/or designs.
97. The Purchaser understands that the engineered flooring system comprises of some natural components and is subject to environmental factors. Indoor and outdoor humidity levels may influence its appearance by way of cupping and/or shrinkage of this material.
98. The purchaser acknowledges that all features are as per applicable plan and are not standard on all plan types.
99. The Vendor shall have the right to at any time without notice to the Purchaser substitute other products and materials for those listed in this Schedule 'A' or provided for in the plans and specifications, provided that the substituted products and materials are of a quality equal to or better than the products and materials so listed or being substituted.
100. Natural or natural simulated or broadloom products (i.e. wood, granite, stone, marble, laminate, engineered flooring, carpeting etc.) are subject to variations in shade, appearance, colour, grain and texture from samples displayed and the Purchaser agrees to accept same notwithstanding any such variations.
101. Due to the nature or the natural grain in wood and the manual process in which stain is applied, there may be some variation in finished colour and texture from prefinished hardwood, including without limitation, stairs, railings, nosings, trim, and pickets.
102. The Purchaser acknowledges that there shall be no reduction in the purchase price or credit for any standard feature listed herein which is omitted at the Purchaser's request.
103. References to model types or model numbers refer to current manufacturer's models. If these types or models shall change, the Vendor shall provide a product of equal or better quality.
104. All dimensions, if any, are approximate, and are subject to change without notice.
105. All specifications and materials are subject to change without notice.
106. Pursuant to this Agreement, including this Schedule or pursuant to a supplementary agreement or purchaser order, the Purchaser may have requested the Vendor to construct an additional feature within the dwelling unit which is in the nature of an optional extra (such as, by way of example only, a media station). If, as a result of building, construction or site conditions, the Vendor is not able to construct or does not construct such extra, then the Vendor may, by written notice to the Purchaser, terminate the Vendor's obligation to construct the extra. In such event, the Vendor shall refund to the Purchaser the monies, if any, paid by the Purchaser to the Vendor in respect of such extra, without interest and in all other respects this Agreement shall continue in full force and effect.
107. Floor and specific features will depend on the Vendor's package as selected.
108. Unless specifically provided for in the purchase agreement, kitchen and laundry appliances, including without limitation, washer/dryer, stove, dishwasher and refrigerator, are not included in the purchase price.
109. Actual useable floor space may vary from stated floor area(s).
110. Errors and Omissions Excepted
111. This Schedule 'A' is subject to the terms and conditions of the Agreement, including Schedule 'B'.





WESTFIELD

FEATURES FOR 34' & 38' SINGLES

GENERAL

1. All interior finishing materials are to be chosen with the assistance of Great Gulf Interior Design Consultants.
2. All materials and other selections for which the Purchaser is entitled to make a selection are to be chosen from Vendor's samples and are as per Vendor's specifications. Purchaser shall only be entitled to make such selections provided that the items are not already ordered or installed.
3. All exterior finishes and colours are selected by the Vendor and are subject to architectural control.
4. Homes are covered with Taron Warranty Corporation's warranty; fee to be paid for by Purchaser on closing.
5. All homes to have blower door test.
6. All homes are third party tested and inspected.

EXTERIORS

7. All model types will be principally brick construction on the first and second floors, as per applicable model elevation.
8. Some sections of the house may be constructed of architectural stone, aluminium or vinyl siding, wood or stucco, as per architectural detailing.
9. Soldier coursing, brick arches, keystones and other masonry detailing as per model / elevation.
10. All soffits, fascias, eaves and down pipes are prefinished aluminium or vinyl at the option of the Vendor.
11. Exterior house address number.
12. Self-sealing limited lifetime warranty laminate shingles.
13. Weather-stripping on all exterior doors and precast stone thresholds.
14. Fibreglass insulated front entry door and "steel-clad" side entry door (as per applicable model/elevation). Glass insert in front entry door, as per applicable/model elevation.
15. All sliding patio doors to be double-glazed, PVC, with low E glass (as per applicable model/elevation)
16. All windows are to be triple -glazed, PVC, with low-E glass. All operating windows are to be screened. All operable windows on the first and second floors will be casement throughout with decorative bars on the front elevation, as per applicable model/elevation.
17. All basement windows to be sliders, double-glazed, PVC, with low-E glass. Corrugated galvanized steel window wells may be required as per grading conditions.
18. Garage overhead metal/insulated door(s) with glazed inserts as per applicable model/elevation.
19. All garage walls to be completed to drywall and primed.
20. Front, rear and side yards, if applicable to be fully sodded. Some side yards to be stone, as per grading conditions.
21. Concrete front entry steps, as per grading conditions.
22. Precast concrete slab walkway to front entry.
23. Exterior cold water tap installed in attached garage and at rear of house, as per applicable model/elevation.
24. Basement to be poured concrete with a drainage layer system and a footing barrier membrane.
25. Vendor will provide a two-coat asphalt driveway at a cost more particularly set out in the Schedule B to the Agreement of Purchase and Sale. Driveway surface to be paved with base coat asphalt within eighteen (18) months of closing and the topcoat to be completed within the next calendar year. Vendor not responsible for minor settlement.
26. All exterior walls, interior partitions and flooring are built using H+ME Technology.

INTERIORS

27. Detached model types to have approximately 9 ft. ceiling heights on the main floor and 8 ft. ceilings on second floor, except where precluded by bulkheads.
28. Finished oak stairs with railings, metal pickets on main floor staircase to second floor with a choice of stain from vendor's standard selection.
29. Two panel square style interior doors.
30. 3" casings on all windows and doors
31. 5 ¼" baseboards (with shoe mould in tiled and hardwood areas)
32. All closets to have wire shelving.
33. Gas fireplace as per applicable model/elevation with 8" marble surround and factory approved safety barrier. Fireplaces are as per applicable model/elevation only.

34. Satin nickel coloured finish hardware on all interior and exterior doors. Dead bolt on side door entry where applicable. Grip set with dead bolt on main entry door, and single lever handles on interior doors.
35. All paint is zero VOC throughout the house.
36. Sprayed stippled ceiling with smooth border in all rooms except the kitchen, bathrooms and laundry room, which are smooth finish.

FLOORING

37. High performance engineered flooring system "1" - joists.
38. O.S.B. Tongue and groove sub floor glued, nailed, and sanded.
39. 3" Prefinished engineered strip hardwood flooring with choice of colour from vendors standard selection, in all areas of the main and second floor, except where shown as tile, as per applicable model/elevation.
40. Floor tile approx. 12" x 24" in foyer, laundry area, and all bathrooms, or as shown on applicable model/elevation.

KITCHEN

41. Choice of finished kitchen cabinets with a dishwasher opening.
42. Single lever chrome flow efficient faucet with a pull-down sprayer.
43. 2cm engineered quartz countertops for kitchen with a square edge (No backsplash) and a double stainless steel undermount sink.
44. Stainless Steel ducted range hood fan over stove.
45. Rough-in plumbing and electrical outlet for dishwasher.
46. Wiring and receptacle for stove.
47. Electrical outlets are located for fridge and at counter level for small appliances.

BATH/PLUMBING

48. Choice of vanity cabinets and 2cm engineered quartz counter tops with a white undermount sink in all bathrooms from Vendor's samples.
49. All bathroom(s) to have a wall-mounted mirror and vanity cabinet as per applicable model / elevation.
50. Ensuite bathroom to have a wall mounted mirror and vanity cabinet with one top drawer as per applicable model/elevation.
51. Master ensuite bathroom to include a white drop-in acrylic soaker tub or a white free-standing acrylic tub with a deck mount faucet as per applicable model. Soaker tub to have a tiled deck and skirt with tile on surrounding wall approximately 18" in height.
52. Master ensuite bathroom to contain a separate framed glass shower enclosure, preformed shower base, walls to be tiled to ceiling, per applicable model/elevation, including waterproof pot light.
53. All bathtub enclosure walls in bathrooms to be tiled.
54. All bathtubs to be white acrylic, as per applicable model/elevation.
55. All toilets are to be white, elongated flow efficient and regular height.
56. Exhaust fan in all bathrooms, vented to the exterior.
57. Privacy locks on all bathroom doors.
58. Single lever chrome flow efficient faucets on all sinks, except laundry tub.
59. Temperature control valves in all showers.
60. Chrome towel bar and toilet paper dispenser in all bathrooms.
61. Main floor powder room to contain a floating vanity cabinet with 2 cm engineered quartz countertop, a white undermount sink, toilet and wall-mounted mirror.
62. Shut off valves for all sinks and toilets.
63. All water lines to be polyethylene tubing throughout.
64. Rough-in three-piece plumbing in basement for future bathroom (drains only, no water lines).

LAUNDRY

65. Second floor laundry room equipped with floor drain as per applicable model/elevation.
66. Laundry room to have a laundry tub or base cabinet with built-in single compartment laundry tub with a two-handle laundry faucet and laminate counter-top, as per applicable model/elevation.
67. Plumbing and electrical outlet for washing.
68. Dryer vent and electrical outlet for future dryer.

ELECTRICAL

69. 200 amp. electrical service.
70. Copper electrical wiring throughout.
71. Electric light fixtures with LED bulbs provided in all rooms except living room, as per applicable model/elevation.
72. Exterior cast aluminium lights with LED bulbs at all exterior doors, as per applicable model/elevation.
73. Two exterior waterproof ground fault circuit Interrupter (GFI) electrical outlets: one (1) at the rear of the house and one (1) in the porch area.
74. White Decora style switches and outlets throughout.
75. Electrical outlet for future garage door opener(s). One outlet for each garage door.
76. Smoke detectors with strobe light hard wired to the electrical system, as per applicable code requirements.
77. Combination smoke detector / carbon monoxide detector hard wired to the electrical system, as per applicable code requirements.
78. Door bells to be installed at front entry /side entry doors as per applicable model.
79. Rough-in vacuum system, located in the basement for future connection as per applicable model/elevation.
80. Rough-in security as per Vendor's specifications (wires to all operable windows and doors on main floor only).
81. Rough-in RG6 cable in family room, master bedroom, loft and study/den, as per applicable model/elevation.
82. Rough-in CAT5 telephone as per Vendor's specifications (one in kitchen, family room, all bedrooms, and den).
83. Rough-in conduit for future installation of an electric vehicle charger located in the garage.
84. A single ground fault interrupter (GFI) protected electrical outlet in all bathrooms.
85. Rough-in conduit for future solar energy.

HEATING, AIR CONDITIONING & INSULATION

86. Direct vent gas-fired high-efficiency forced air furnace with ECM (Electronically Commutated Motor) and includes a programmable thermostat installed. Hot water heater on a rental basis. Note: All mechanical equipment locations may vary from plan.
87. Heat Recovery Ventilator (HRV) as per the Ontario Building Code requirements
88. HVAC ducts are sized for future addition of air conditioning.
89. All insulation to be as per the Ontario Building Code requirements.
90. Basement insulation to be installed to within approximately 8" above the basement slab in the basement area. Note: Basement walls are not strapped.
91. Spray foam insulation to garage ceiling below any habitable space above.

GENERAL PROVISIONS

92. The Purchaser hereby acknowledges and agrees that due to, without limitation, grading, drainage, building code requirements, municipal setback requirements, or other conditions or issues, the Vendor, in its sole discretion, may make changes to modify the floorplan, add and/or adding and or/eliminate doors or steps without adjustment to the purchase price and without further notice to the Purchaser, including without limitation:
 - a. Eliminating the door between the garage and the laundry/utility room;
 - b. Eliminating the side door;
 - c. Installing step(s) with or without a railing in the garage due to different grading may interfere with or limit the use of the interior of the garage;
 - d. Lowering or creating a step down into the laundry/utility room to accommodate the garage door and/or side door to the laundry/utility room;
 - e. Lowering or creating a step down into the foyer
 - f. Installing or eliminating a deck depending upon the grading requirements for that particular lot;
 - g. Entry steps may be required, varied, and/or eliminated to the house.

93. The Purchaser acknowledges that finishing materials contained in any model home or sales office display including but not limited to, broadloom, furniture, electrical fixtures, drapes, ceramic flooring, upgrades kitchen cabinets, stained staircases, railing, wallpaper, paint, landscaping and fencing, may be for display purposes only and may not be of the same grade or type, or may not be included in the dwelling unit purchased herein.
94. Interior design consultation at The Design Studio on all finishes and colour packages included in purchase price. All interior floor, wall finishes and materials are to be chosen with the assistance of the Vendors Interior Design Consultant. All materials and other selections for which the Purchaser is entitled to make a selection are to be chosen from Vendors samples, and are as per Vendor's specifications. Purchaser shall only be entitled to make such selections provided that the items are not already ordered or installed.
95. Purchaser acknowledges the right reserved and/or easement in favour of the Vendor permitting entry for installation of berms, fences and/or landscaping, and the purchaser further acknowledges their undertaking to maintain the berms, fences and/or landscaping after installation.
96. The Purchaser acknowledges that the Vendor will only replace any obvious floor tile damages caused by settlement within the first year of closing, provided the Vendor is able to match the floor tile dye lots, colours and/or designs.
97. The Purchaser understands that the engineered flooring system comprises of some natural components and is subject to environmental factors. Indoor and outdoor humidity levels may influence its appearance by way of cupping and/or shrinkage of this material.
98. The purchaser acknowledges that all features are as per applicable plan and are not standard on all plan types.
99. The Vendor shall have the right to at any time without notice to the Purchaser substitute other products and materials for those listed in this Schedule 'A' or provided for in the plans and specifications, provided that the substituted products and materials are of a quality equal to or better than the products and materials so listed or being substituted.
100. Natural or natural simulated or broadloom products (i.e. wood, granite, stone, marble, laminate, engineered flooring, carpeting etc.) are subject to variations in shade, appearance, colour, grain and texture from samples displayed and the Purchaser agrees to accept same notwithstanding any such variations.
101. Due to the nature or the natural grain in wood and the manual process in which stain is applied, there may be some variation in finished colour and texture from prefinished hardwood, including without limitation, stairs, railings, nosings, trim, and pickets.
102. The Purchaser acknowledges that there shall be no reduction in the purchase price or credit for any standard feature listed herein which is omitted at the Purchaser's request.
103. References to model types or model numbers refer to current manufacturer's models. If these types or models shall change, the Vendor shall provide a product of equal or better quality.
104. All dimensions, if any, are approximate, and are subject to change without notice.
105. All specifications and materials are subject to change without notice.
106. Pursuant to this Agreement, including this Schedule or pursuant to a supplementary agreement or purchaser order, the Purchaser may have requested the Vendor to construct an additional feature within the dwelling unit which is in the nature of an optional extra (such as, by way of example only, a media station). If, as a result of building, construction or site conditions, the Vendor is not able to construct or does not construct such extra, then the Vendor may, by written notice to the Purchaser, terminate the Vendor's obligation to construct the extra. In such event, the Vendor shall refund to the Purchaser the monies, if any, paid by the Purchaser to the Vendor in respect of such extra, without interest and in all other respects this Agreement shall continue in full force and effect.
107. Floor and specific features will depend on the Vendor's package as selected.
108. Unless specifically provided for in the purchase agreement, kitchen and laundry appliances, including without limitation, washer/dryer, stove, dishwasher and refrigerator, are not included in the purchase price.
109. Actual useable floor space may vary from stated floor area(s).
110. Errors and Omissions Excepted
111. This Schedule 'A' is subject to the terms and conditions of the Agreement, including Schedule 'B'.

